(*g*) That no timber prepared out of any tree shall be removed unless it is measured and stamped at the stump by the Range Officer, or such other Officer deputed by the District Forest Officer in this behalf.

(*h*) That each consignment of timber shall be covered by a passport issued by the Range Officer or any other officer deputed by the District Forest Officer in this behalf.

(*i*) That he shall abide by the rules of the Department as regards the kindling of fires and shall hold himself responsible for any forest offences committed by his agents, employees or workmen.

(*j*) That if any trees other than the one bearing the departmental stamp or a tree that has not been purchased is felled, he shall pay a fine not exceediig Rs. 15 for each such tree.

(*k*) That no operations shall take place in the forest after sunset or before sunrise.

(*l*) That he shall have no right whtasoever over the coupe and over the timber left unremoved in any of the coupes after the 30th June 1939.

(*m*) That he shall not sublet the contract to anybody except with the written sanction of the District Forest Officer.

(*n*) That he shall maintain a register in the form prescribed by the District Forest Officer showing the number of trees felled and the outturn of timber from each of them and shall keep it open for the examination of Forest Officers above the grade of guards.

(*o*) That for any breach of any of the conditions of the contract by the contractor or his agents, the contract shall be void at the option of the District Forest Officer and that the latter may, after issuing to the contractor, a notice of cancellation of contract, enforce forfeiture of all or any part of the deposit and shall resell the right or work it departmentally at the risk of the contractor as in clause (2) *supra*. If the deposit or part thereof is so forfeited, it shall be immediately made good by the contractor.

N. VENKATARAMAIYA,
District Forest Officer.

ENGINEERING DEPARTMENT.

KOLAR DIVISION.

Notification dated 13th January 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 12 noon on 8th February 1939, for restoration of Vokkaleri Hirekere Major Tank, Register No. 204—84 of Kolar Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer Kolar Division, in a sealed cover and superscribed as "Tender for restoring Vokkaleri Hirekere." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by treasury challan for earnest money of Rs. 465 paid to the treasury to the credit of 17 (A) P. W. Deposits against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 8th February 1939 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931) and also furnish a security deposit of Rs. 930.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page, noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of February 1940, failing which, the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N.B.—Copies of prescribed tender form may be obtainable from the Office of the Executive Engineer, Kolar Division, only on payment of Re. 0-4-0 per form.

Amount of estimate Rs. 9,330.

Abstract estimate for restoring Vokaleri Hirikere Register No. 204—84, Major Tank, Kolar Taluk.

No.	Items of work	Unit	Rate	Quantity	Tendered rate
			Rs. a. p.		Rs.
	I. Bund R.L. 56.00, Top-width 6 ft.				
1	Jungle clearing and removing ant hills and filling them with sand and good earth	Grade	1 0 0	36	
2	Removing top soils and cutting trenches and grips to bund to a depth of 1′×1½′ to receive new earth	,,	3 0 0	36	
3(*a*)	Earthwork to bund with watering and consolidation	C.yd.	0 3 0	7,841	
(*b*)	Earthwork to bund with earth available from waste weir including lead, watering and consolidation.	C.yd.	0 1 6	1,597	
4	Turfing the slopes close by packing with turf ..	Sq.yd.	0 0 9	8,118	
5	Gravel backing 9″ thick with consolidation ..	C.yd.	0 6 0	334	
6	Rough stone revetment with new stones with 1 mile bed including new jelly packing ..	,,	1 8 0	712	
7	Earth excavation in old bund for seat of revetment to required slope and using the earth to the bund	,,	0 3 0	534	
8	Removing and resetting old stone revetment to the proper slope with new jelly packing ..	,,	0 8 0	100	
9	Removing and refixing the existing grade stones including carving figures, painting and providing bed slabs, etc., complete	Each	0 8 0	30	
10	Providing and fixing new grade stones with bed slab including carving figures and painting ..	,,	1 8 0	7	
11	Providing and fixing Index stones (new) ..	,,	0 6 0	37	
12	Providing and fixing gauge stones including carving figures painting ,etc., complete	,,	15 0 0	1	
13	Providing and fixing register No. and date stone with carving letters, etc., and painting ..	,,	3 0 0	1	
14	Removing and refixing existing B. M. stones after painting, etc., complete to the given level in concrete with bed slab	,,	0 8 0	2	
	Total ..				
	II(a). Constructing a cast iron pipe sluice at R.L. 43.50.				
1	Earthwork cut opening the bund and refilling the same with watering and consolidation (including steps and grips)	C.yd.	0 5 6	208	
2	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 4 0	259	
3	Burnt size stone in surki mortar	,,	0 5 0	371	
4	Burnt stone slabs 4″ thick dressed fixed ..	Sq.ft.	0 4 0	342	
5	Pointing with cement mortar including racking joints	Sqr.	4 0 0	4·28	
6	Drilling holes in slabs	L. S.	..	..	
7	Providing plug and rod with locking arrangements, etc., complete	Each	15 0 0	1	
8	Providing and fixing cast iron pipes 8″ diameter including railway freight cart hire, fixing in position etc., complete	R.ft.	2 12 0	36	
9	Dismantling the existing sluice	C.ft.	0 0 3	..	
	Total ..				
	(*b*) *Constructing a second sluice at 44.20 R.L. as per above.*				
	III. Constructing a waste-weir at R.L. 52.00 and 400 ft. long.				
1	Earthwork excavating foundation	C.yd.	0 3 0	708	
2	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 4 0	1,053	
3	Burnt size stone in surki mortar	,,	0 5 0	2,199	

No.	Items of work	Unit	Rate	Quantity	Tendered rate
			Rs. a. p.		Rs.
4	Burnt stone slab 6″ thick dressed and fixed	Sq.ft.	0 5 0	632	
5	New stone work with one mile lead for stone and new jelly backing and packing	C.yd.	1 8 0	523	
6	Pointing with cement mortar	Sqr.	4 0 0	26.78	
7	Providing joggle joint	Each	0 12 0	49	
8	Earth excavation for draft clearing	C.yd.	0 3 0	889	
9	Clay for ramp including spreading consolidation with lead of ½ mile	C.yd.	0 8 0	58	
	Total				
	IV. Raising Kolar-Malur—Hosur Road.				
1	Picking the existing road surface to 6″ depth	C.yd.	0 2 6	383	
2	Earthwork embankment raising the road with consolidation	,,	0 3 0	945	
3	Turfing the slopes	Sq.yd.	0 0 9	675	
4	(*a*) Collecting and stacking burnt metal 1″ to 1½ size.	C.yd.	1 4 0	128	
	(*b*) (Lead for metal 3¼ miles)	,,	1 5 3	128	
	(*c*) Collecting and stacking gravel	,,	0 3 6	64	
	(*d*) Lead for gravel ⅞ mile	,,	0 6 6	64	
	(*e*) Spreading and consolidating metal	,,	0 4 6	128	
	(*f*) Spreading and consolidating gravel	,,	0 3 6	64	
	(*g*) Collecting and spreading sand	,,	0 4 0	7	
	(*h*) Water charges	,,	0 1 9	128	
5	Improving the existing two culverts	L. S.	..	..	
	Total				

Notification dated 12th January 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 12 NOON on 8th February 1939 for constructing Hostel buildings attached to the Agricultural Middle School at Kagathi, Chintamani Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for Hostel buildings at Kagathi." The name of the tenderer should also superscribed on the top of the cover.

3. Each tender must be accompanied by treasury challan for earnest money of Rs. 460 paid to the treasury to the credit of 17 (*a*) P. W. deposits against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers as wish to be present on 8th February 1939, at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the Departmental Schedule Contract form for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931) and a security deposit of Rs. 920 also furnished.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page, noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of December 1939, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.

(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.

(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.

(4) Arrange for protecting work during inclement weather.

(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.

(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.

(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by Insurance at the proper time.

(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

(*c*) Copies of tenders in the prescribed from are abtainable from the Office of the Executive Engineer, Kolar Division, only on payment of Re. 0-4-0 per form.

Abstract estimate for constructing Hostel buildings attached to the Agricultural Middle School at Kagathi in Chintamani Taluk.

No.	Items of work	Unit	Rate	Quantity	Rate to be tendered
	I. Hostel Building.		Rs. a. p.		Rs.
1	Earthwork excavation for foundation and filling in basement	C.yd.	0 3 0	19	
2	Laying stone jelly concrete in chunam mortar	C.ft.	0 3 6	1,023	
3	Size stone in mud foundation	,,	0 3 0	1,532	
4	Size stone in mud basement, including dressing quoins, etc., complete	,,	0 3 3	873	
5	Burnt brick in mud superstructure	,,	0 3 0	3,560	
6	Burnt stone slabs 6″ thick exposed surface 1 line dressed and fixed	Sq.ft.	0 4 6	516	
7	Teakwood doors with panelled shutters 1½″ thick including top ventilators glazed and all iron fittings, etc., complete	,,	1 6 0	204	
8	Teakwood windows with panelled shutters and top glazed ventilators including iron bars, bolts, etc., complete	,,	1 10 0	303	
9	Teakwood ventilators with glazed shutters including iron bars, etc., complete	,,	1 2 0	32	
10	Teakwood wrought and put up including wood oiling	C.ft.	5 0 0	115	
11	Roofing with first class Mangalore tiles including teakwood reepers, etc., complete	Sqr.	26 0 0	16.26	
12	Ridge tiles set in mortar including pointing	R.ft.	0 7 0	203	
13	Plastering with chunam mortar	Sqr.	3 0 0	61.59	
14	White-washing, 2 coats	,,	0 4 0	62.00	
15	Burnt brick in chunam mortar, pillars 1½′ sqr. and 9½ ft. high including base and capital and plastering, etc., complete	Each	10 0 0	10	
16	R. S. Beams of B. S. specifications including hoisting and fixing with a prime coat of anti-corrosive paint	Cwt.	12 0 0	8.2	
(*a*)	Boxing R. S. Beams with burnt brick in cement mortar (1 : 5) and plastering, etc., complete	R.ft.	0 10 0	77	
17	Roofing with R. C. C. including tension and compression bars as per specification in force	Sqr.	70 0 0	5.26	
18	R. C. C. chajja including plastering, etc., complete.	C.ft.	1 0 0	167	
19	Flooring with chunam mortar concrete 3″ thick with stone jelly and plastering with ¾″ thick cement mortar (1 : 3) and rendering surface red including cutting lines	Sqr.	17 0 0	13.84	
20	Providing T. W. plain eaveboard 9″ deep and ¾″ thick including painting, etc., complete	R.ft.	0 7 0	260	
21	Chunam mortar pointing to basement	Sqr.	1 8 0	3.76	
22	Lac Factory green painting (2 coats) or any approved paint to doors and windows	,,	3 8 0	9.12	
23	Clearing site and levelling ground, etc., complete	L. S.			
	Total				
	II. Kitchen.				
1	Earthwork excavation in ordinary soil and filling in basement	C.yd.	0 3 0	35	
2	Burnt stone jelly concrete in lime mortar	C.ft.	0 4 0	473	
3	Burnt size stone in clay	,,	0 3 0	846	
4	Burnt brick in clay	,,	0 3 6	1,696	
5	Burnt brick in lime mortar	,,	0 4 6	353	
6	Burnt stone slabs 6″ thick dressed and fixed	Sq.ft.	0 5 0	135	
7	Teak battened doors with shutters and iron fittings, etc., complete	,,	1 4 0	58½	
8	Teakwood windows with battened shutters including iron bars and fittings, etc., complete	,,	1 12 0	60	
9	T. W. ventilators with glass shutters and iron bars.	,,	1 8 0	21	
10	Teakwood wrought and put up including wood ciling	C.ft.	5 0 0	40.18	
11	Roofing with first class Mangalore Tiles on 2″×1″ reepers including fixing, etc., complete	Sqr.	26 0 0	12.58	
12	Ridge tiles set in mortar	R.ft.	0 7 6	43	

No.	Items of work	Unit	Rate	Quantity	Rate to be tendered
			Rs. a. p.		Rs.
13	Chunam borders 9″×4½″ with burnt brick in mortar	R.ft.	0 4 0	60	
14	Flooring with 3″ thick concrete in chunam mortar and cement plastering ¾″ thick	Sqr.	12 0 0	7·29	
15	Plastering with lime mortar	,,	3 0 0	37·72	
16	Teakwood plain eaveboard 9″ deep and ¾″ thick including painting, etc., complete	R.ft.	0 7 0	86	
17	Pointing with chunam mortar	Sqr.	1 8 0	1·21	
18	Chocolate or any other approved painting, 2 coats ..	,,	3 0 0	3·10	
19	White-washing, 2 coats	,,	0 4 0	37·72	
20	Providing sinks in Bath and Kitchen rooms and smoke escapes, etc., complete	L. S.	..	..	
21	Constructing drains to lead off water	,,	..	..	
22	Clearing site and levelling ground	,,	..	..	
	Total ...				
	III. Granary and Bullock-shed.				
1	Earthwork excavation and filling in basement including tamping, etc., complete	C.yd.	0 3 0	20	
2	Laying burnt stone jelly concrete in chunam mortar	C.ft.	0 3 6	135	
3	Size stone in clay foundation and basement ..	,,	0 3 3	497	
4	Burnt brick in mud superstructure	,,	0 3 0	1,398	
5	Burnt stone slabs 6″ thick roughly dressed and fixed	Sq.ft.	0 4 0	89	
6	Teakwood doors with battened shutters including bolts, hinges and all iron fittings, etc., complete	,,	1 4 0	49	
7	Teakwood windows with battened shutters including ¾″ dia. iron bars, bolts and hinges, etc., complete	,,	1 8 0	54	
8	Teakwood ventilators with glazed shutters including iron bars, etc., complete	,,	1 2 0	18	
9	Teakwood wrought and put up including wood oiling	C.ft.	5 0 0	40·73	
10	R. S. joists 4″×8″ including hoisting, fixing and painting, etc., complete	Cwt.	12 0 0	2	
11	Roofing with Ist class Mangalore Tiles including T. W. reepers, etc., complete	Sqr.	26 0 0	8·14	
12	Ridge tiles set in mortar including cement pointing	R.ft.	0 7 0	76	
13	Plastering with chunam mortar	Sqr.	3 0 0	28·47	
14	White-washing, 2 coats	,,	0 4 0	28·47	
15	Flooring with burnt stone slabs on a bed of 3″ concrete including cement pointing, etc., complete	,,	30 0 0	1·98	
16	Flooring with 3″ thick stone jelly concrete and cement plastering, etc., complete	,,	8 0 0	1·61	
17	Providing R. C. C. slab 3 to 4½″ thick with manholes in the centre including plastering, etc., complete	C.ft.	1 4 0	37	
18	Providing and fixing T. W. eaveboard 9″ deep and ¾″ thick including painting, etc., complete ..	R.ft.	0 7 0	116	
19	Teakwood finials including fixing and painting, etc., complete	Each	1 0 0	2	
20	Chocolate painting, 2 coats	Sqr.	3 0 0	1·91	
21	Providing expanded metal enclosure with T. W. frame including painting, etc., complete ..	Sq.ft.	0 10 0	79	
22	Cement pointing to basement	Sqr.	3 12 0	1·49	
23	Providing Iron Trap doors with frame and sliding shutters 6″×9″ for granary cells	Each	3 0 0	5	
24	Providing 1½′ to 2′ dia. gratings (iron) to manholes in the centre of R. C. C. covering slab including locking arrangements, etc., complete ..	,,	2 0 0	5	
25	Constructing ramp with a gentle slope	L. S.	..	..	
26	Constructing drain and urine pit with brick in cement mortar	,,	..	..	
	Total ..				
	IV. Sinking a well in the compound	L. S.	..	..	
	V. Construction of a latrine	,,	..	..	
	Total ..				

R. TIPPAIYA,
Executive Engineer.